

Guide to Assembly & Usage

BiG400 3 Level Workstation with Half Depth Lower Shelf Assembly

Information
If in doubt, contact the supplier

Read this guide thoroughly before commencing assembly and retain for future reference

Before commencing assembly, unpack carefully and check that all components ordered are included

Assembly should be undertaken by a minimum of two competent people

Tools – Rubber Mallet

Caution
During assembly, ensure to:

Take care during assembly and in use, particularly when lifting or stretching and when using tools

Wear appropriate clothing - protective gloves and footwear are recommended

Build on a suitable level floor, which is strong enough to support the load and allow adequate working space

Dispose of packaging materials responsibly

Warning
Rules for safe use of workstations:

Ensure these instructions are retained for reference and that users are aware of the rules for safe use

Never climb on the structure or stand on the workstations

Do not lean or support ladders, steps, or other objects against workstations

Do not use in damp or wet conditions

This product is designed for hand loading only

Ensure that the maximum load carrying capacities are not exceeded

Loading information

BiG400 3 Level Workstation with Half Depth Lower Shelf
Shelf load capacities
Maximum permitted shelf capacities are based on UDL†.
















BiG400 3 Level Workstation with Half Depth Lower Shelf	
Shelf	Load Capacity per shelf
Top Shelf	100kg
Worktop	400kg
Lower Shelf	200kg

IF YOU ARE IN ANY DOUBT REGARDING LOAD CAPACITIES, PLEASE CONTACT YOUR SUPPLIER

†UDL = Uniformly Distributed Load



COMPONENT CHECK LIST

Component		Quantity
A Plastic Foot		4
B Plastic Top Cap		4
C Upright 915mm		2
D Upright 1295mm		2
E 'L' Beam (short)		2
F 'T' Beam (short)		2
G 'C' Beam		3
H 'L' Beam (long)		1
I Cantilever Beam		1
J Centre Support (galvanised)		1
K Centre Support (orange)		1
L 15mm Chipboard Deck		2
M Lower Shelf		1
N Top Shelf		1
O Chipboard Joiner		1

If you have any missing components please take note of the part name and contact your supplier.

Assembly - BiG400 3 Level Workstation with Half Depth Lower Shelf

